



Public Works works for the Public



COUNTY OF
IMPERIAL

COUNTY OF IMPERIAL PUBLIC WORKS

**Bowker Rd. Rehabilitation from McCabe Rd. to Ross Rd. in Imperial County;
Federal Project No. STPL-5958(130); County Project No. 6959**

ADDENDUM NO. 3

May 19, 2025

This *ADDENDUM* is hereby made part of the Contract Documents and specifications to the same extent as if originally included therein and shall be signed by the Bidder and included with the proposal.

1. Replace Section 7-1.02K(6)(j)(ii) with:

Section 7-1.02K(6)(j)(ii) a lead compliance plan shall be prepared by contractor for this project.

Regulations containing specific Cal/OSHA requirements when working with lead include 8 CA Code of Regs § 1532.1.

Submit a plan:

1. That documents your compliance program to prevent or minimize worker exposure to lead
2. Including the items listed in 8 CA Code of Regs § 1532.1(e)(2)(B)
3. Sealed and signed by a CIH with knowledge of and experience complying with 8 CA Code of Regs Allow 7 days for review. Obtain authorization for the plan before starting any activity that presents the potential for lead exposure.

Before starting any activity that presents the potential for lead exposure to employees who have no prior training, including County employees, provide a safety training program to these employees that complies with 8 CA Code of Regs § 1532.1 and your lead compliance plan.

Submit copies of air monitoring or job site inspection reports made by or under the direction of the CIH under 8 CA Code of Regs § 1532.1 within 10 days after the date of monitoring or inspection.

Supply personal protective equipment, training, and washing facilities required by your lead compliance plan for 5 County employees.

Payment

Full compensation for preparation of a Lead Compliance Plan shall be considered as included in the above contract prices and payments paid per lump sum for "Road Striping and Signage" and no separate or additional payment shall be considered therefor.

- 2. Question:** "Could you clarify if the pavement markings and striping shall be in 2 coat paint or thermoplastic? Also, the striping details that are being listed have no pavement markers, but in the specs, it mentions in section 12-4.02C(7)(a), "pavement marker placement using bituminous adhesive. Will the striping require raised pavement markers? Following that, do the existing stripes and markings need to be removed prior to AC grinding??"

Response:

All striping shall be completed with a two layers coat paint and reflective glass beads see sections 84-2.02G and 84-2.03B(6) of the Caltrans Standard Specifications.

155 S. 11th Street
El Centro, CA
92243

Tel: (442) 265-1818
Fax: (442) 265-1858

Follow Us:



[www.facebook.com/
ImperialCountyDPW/](https://www.facebook.com/ImperialCountyDPW/)



[https://twitter.com/
CountyDpw/](https://twitter.com/CountyDpw/)

The existing striping does not have raised pavement markers. The plans and specifications do not require raised pavement markers.

The Resident Engineer shall determine if existing striping will be required to be removed prior to Grinding existing A.C. pavement.

Atondo V. #012

John A. Gay, P.E.
Director of Public Works

Acknowledgement of Addendum No. 3

The general contractor is responsible for advising any and all subcontractors of this change. Each prime consultant must acknowledge receipt of this addendum in the noted space below. This Addendum must be attached to the proposal.

License No: _____

Print or Type Company Name: _____

Print or Type Authorized Name: _____

Authorized Signature of Contractor: _____

Date Signed: _____