



COUNTY OF  
IMPERIAL

DEPARTMENT OF  
PUBLIC WORKS

155 S. 11th Street  
El Centro, CA  
92243

Tel: (442) 265-1818  
Fax: (442) 265-1858

Follow Us:



[www.facebook.com/  
ImperialCountyDPW/](https://www.facebook.com/ImperialCountyDPW/)



[https://twitter.com/  
CountyDpw/](https://twitter.com/CountyDpw/)



*Public Works works for the Public*

## COUNTY OF IMPERIAL PUBLIC WORKS

**Imperial County Road Rehabilitation for Various County Roads at Gateway of the Americas: County Project No. 6622GTW.**

### **ADDENDUM NO. 3**

**July 30, 2025**

This *ADDENDUM* is hereby made part of the Contract Documents and specifications to the same extent as if originally included therein, and shall be signed by the Bidder and included with the proposal.

1. **Bid opening date has been postponed until August 7, 2025 at 3:00 p.m.**
2. **REPLACE the Bid Item List on Page 2 of the Notice to Bidders of the project specifications with the revised Page 2 Bid Item List attached to this Addendum.**
3. **REPLACE the Bid Item List on Page 58 of the Division XIV Bid Proposal of the project specifications with the revised Bid Item List Page 58 attached to this Addendum.**
4. **REPLACE SECTION: TIME AND MATERIAL ALLOCATION (Page 18 Control of Work) with**

The Contractor shall provide a rate schedule for all labor and equipment that may reasonably be anticipated for use during the project. Labor rates shall be consistent with those required by the prevailing wage rate requirements of the contract and shall reflect all benefits and employer costs. Once the labor and equipment rates have been approved by the engineer, they will become the basis for compensation for any Time and Material work requested by the County. The Contractor is advised, however, that there will be no compensation from the Time and Material Allocation unless the work has been authorized in writing by the engineer. Additionally, use of the Time and Material Allocation will be at the sole discretion of the County. All or any portion of the allocation amount may be deleted from the Contract. The Time and Material allocation for this project shall be \$100,000. This is the number to be used for the bid proposals schedule.

**5. REPLACE SECTION 37-6.04 with (Page 51 Division V Surfacing and Pavements):**

**PAYMENT**

Full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in furnish, prepare, clean, and seal all cracks, complete in place, as shown on the plans, as specified in these special provisions, and as directed by the Engineer shall be considered as included in the contract price paid per square yard of Crack Treatments, and no separate or additional payment shall be considered therefor. The square yardage is the area of entire paved road surface the crack treatments are to be placed.



John A. Gay, P.E.  
Director of Public Works

**Acknowledgement of Addendum No. 3**

**The general contractor is responsible for advising any and all subcontractors of this change. Each bidder must acknowledge receipt of this addendum in the noted space below and where indicated on the Bidder's Proposal Section of the Special Provisions. This Addendum must be attached to the proposal.**

License No: \_\_\_\_\_

Print or Type Company Name: \_\_\_\_\_

Print or Type Authorized Name: \_\_\_\_\_

Authorized Signature of Contractor: \_\_\_\_\_

Date Signed: \_\_\_\_\_

## BID ITEM LIST

Item No.	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY
1	Mobilization	LS	1
2	Erosion Control, Water Pollution Control and Dust Control	LS	1
3	Construction Area Signs and Temporary Traffic Control	LS	1
4	Install Type II Slurry Seal (135,000 SF)	SY	15,000
5	Crack Seal	SY	54,000
6	Sawcut AC Pavement	LF	700
7	Cold Plane AC Pavement Joint	SF	1,400
8	2" Cold Plane Existing Asphalt Concrete Pavement (350,000 SF), Including Disposal	SY	38,900
9	Demolition/Removal of Existing AC and Undelaying Base Material at Dig Out Areas	CY	80
10	Subgrade Preparation of Dig Out Areas. Re-Compact Subbase in 6" Lifts	SY	170
11	Install Class II Base at Dig Out Areas	CY	60
12	2" of 3/4" HMA Type A Mix	TON	4,600
13	Double Adjust Sewer/Storm Drain Manhole Rim with New Concrete Collar	EA	24
14	Double Adjust Water Valve Can with New Concrete Collar	EA	55
15	Signing, Striping and Pavement Markers	LS	1
16	Monument Preservation/Perpetual	LS	1
17	Material Testing	LS	1
18	Construction Staking	LS	1
19	Time and Material Allocation	LS	1

Plans, specifications, and proposal forms (bid documents) for bidding this project can be obtained at the office of the Imperial County Department of Public Works; 155 South 11th Street, El Centro, CA 92243. A \$100.00 fee is required (no refund will be made). Mail service is available at an additional cost of \$15.00 per set of documents. Make checks payable to the County of Imperial Department of Public Works.

### BID ITEM LIST

Item No.	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL
1	Mobilization	LS	1	\$	\$
2	Erosion Control, Water Pollution Control and Dust Control	LS	1	\$	\$
3	Construction Area Signs and Temporary Traffic Control	LS	1	\$	\$
4	Install Type II Slurry Seal (135,000 SF)	SY	15,000	\$	\$
5	Crack Seal	SY	54,000	\$	\$
6	Sawcut AC Pavement	LF	700	\$	\$
7	Cold Plane AC Pavement Joint	SF	1,400	\$	\$
8	2" Cold Plane Existing Asphalt Concrete Pavement (350,000 SF), Including Disposal	SY	38,900	\$	\$
9	Demolition/Removal of Existing AC and Undelaying Base Material at Dig Out Areas	CY	80	\$	\$
10	Subgrade Preparation of Dig Out Areas. Re-Compact Subbase in 6" Lifts	SY	170	\$	\$
11	Install Class II Base at Dig Out Areas	CY	60	\$	\$
12	2" of 3/4" HMA Type A Mix	TON	4,600	\$	\$
13	Double Adjust Sewer/Storm Drain Manhole Rim with New Concrete Collar	EA	24	\$	\$
14	Double Adjust Water Valve Can with New Concrete Collar	EA	55	\$	\$
15	Signing, Striping and Pavement Markers	LS	1	\$	\$
16	Monument Preservation/Perpetual	LS	1	\$	\$
17	Material Testing	LS	1	\$	\$
18	Construction Staking	LS	1	\$	\$
19	Time and Material Allocation	LS	1	\$ 100,000	\$

Total Bid \_\_\_\_\_